

Kerite Cable Services Project Profile

Project	Snake River Sporting Club
Client	Snake River Sporting Club
Location	Jackson, WY
Cable Design	138 kV, 1250 CU — High Voltage Cable
Length	9,200 Circuit feet
Subcontractors(s)	Anderson & Wood
Scope	Installed a complete 138 kV high voltage circuit across a newly developed golf course. KCS along with our subcontractor built 9,200 feet of concrete encased ductbank including 7 pre-cast splicing vaults. We pulled in 18 lengths of 138 kV cable and built 15 hand-tape splices. Two termination dead-end structures were erected. We installed 6 extended creepage terminations and cross bonded the cable shield. A 24 core fiber optic cable was also installed in the newly constructed ductbank. Final system Hi-pot acceptance testing was completed by KCS technicians. As-built drawings were generated.



Cable Pulling



Ductbank Construction