

Kerite Cable Services Project Profile

Project	Entergy – New Orleans
Client	Entergy
Location	New Orleans, Louisiana
Cable Design	138kV, 500kcmil Cu – High Voltage Cable
Length	3,400 circuit feet
Subcontractors(s)	None KCS was a subcontractor to Welsbach Electric
Scope	Witnessed the pulling of twelve lengths of cable. Cables were pulled with three cables in a single six inch duct. KCS technicians constructed twelve high voltage cable terminations, six pre-molded splices and installed all required sheath bonding accessories. A final system DC–High Pot acceptance test was completed by KCS technicians.



Pulling three cables into a single 6 inch conduit.



Completed terminations.