

Kerite Cable Services Project Profile

Project	Ansonia Substation-Capacitor Bank Addition
Client	United Illuminating-Avangrid
Location	Ansonia, CT
Cable Design	115kV, 750kcmil CU
Length	340 circuit feet
Subcontractors(s)	Central Connecticut Cable Co., Inc.
Scope	Installation of a single 115kV circuit. Scope included pulling three 340ft lengths of cable, performing 10kV jacket integrity test, assembling six G&W PAT130C Dry Type Polymer Terminations and completing a DC Hi-pot test at 226kV DC



Assembling G&W Dry Type Terminations



Preconstruction Meeting

