

Kerite Cable Services Project Profile

Project	Circuit 937
Client	NYSE&G
Location	Town of Ontario, New York
Cable Design	115kV, 2000 kcmil Cu – High Voltage Cable
Length	Two circuits: the first 600 circuit feet and the second 200 circuit feet
Subcontractors(s)	Welsbach Electric Corp.
Scope	Pulled six lengths of cable through an existing duct bank. Performed a 10kV jacket test on each length of cable. Installed twelve high voltage cable terminations and all required sheath bonding accessories. Upon completion of installation, a final system acceptance test was conducted by KCS technicians.



Setting of high voltage termination



Completed high voltage termination

