

## Kerite Cable Services Project Profile

<b>Project</b>	Dynegy Midwest Generation Inc.
<b>Client</b>	Omni Cable Corp.
<b>Location</b>	Baldwin, Illinois
<b>Cable Design</b>	138kV, 500 kcmil Cu — High Voltage Cable
<b>Length</b>	250 Circuit feet
<b>Subcontractors(s)</b>	Client supplied (PMC)
<b>Scope</b>	Supervised cable pulling through existing duct bank. Performed a 10kV-DC jacket test. Installed six high voltage terminals and sheath bonding accessories. Upon completing of the installation, a final system acceptance test was conducted by KCS technicians.



Cable pulling.



Completed terminations.