

Kerite Cable Services Project Profile

Project	Bucksport Generation 115kV Installation
Client	Bucksport Generation
Location	Bucksport, ME
Cable Design	115kV, 1500 kcmil CU
Length	1100 circuit feet
Subcontractors(s)	State Electric Corporation
Scope	Installation of a single 115kV circuit. Scope included pulling three 1,100ft lengths of cable, performing 10kV jacket integrity test, assembling six G&W PAT140 Outdoor In Air Polymer Terminations and completing a DC Hi-pot test at 226kV DC



Concrete encased duct bank



115kV termination riser structure

