

Kerite Cable Services Project Profile

Project	Pittsfield Substation
Client	NUSCO
Location	Pittsfield, MA
Cable Design	115 kV, 1500 CU — High Voltage Cable
Length	700 Circuit feet
Subcontractor(s)	Central Connecticut Cable Company
Scope	Installed one new high voltage underground connection to a capacitor bank within an existing substation. This included the inspection of the existing duct system and pulling in three lengths of cable. Six terminations were installed and the final system Hi-pot acceptance testing was completed by KCS technicians.



Termination Installation



Cable Termination Structure