

Kerite Cable Services Project Profile

Project	Kibby Wind Farm
Client	Cianbro
Location	Coburn Gore, Maine
Cable Design	115 kV, 2000 kcmil Cu — High Voltage Cable
Length	1970 Circuit feet
Subcontractors(s)	McPhee Electric
Scope	Pulled six lengths of cable through an existing duct bank. Performed a jacket test on each length of cable. Installed three splices, six high voltage cable terminations and all required sheath bonding accessories. Upon completion of the installation, a final system acceptance test was conducted by KCS technicians.



Completed 115 kV splices.



Pulling 115 kV cable.