

Kerite Cable Services Project Profile

Project	Dynegy Midwest Generation Inc.
Client	Omni Cable Corp.
Location	Baldwin, Illinois
Cable Design	138kV, 500 kcmil Cu — High Voltage Cable
Length	Two Circuits: the first 650 Circuit feet and the second 310 Circuit feet
Subcontractors(s)	Client supplied (PMC)
Scope	Supervised cable pulling through existing duct bank and Trenwa precast concrete trench. Performed a 10kV-DC jacket test. Installed twelve high voltage terminals and sheath bonding accessories. Upon completion of the installation, a final system acceptance test was conducted by KCS technicians.



Completed terminations.



Cable pulled into ducts.