

Kerite Cable Services Project Profile

Project	Spurlock Substation
Client	East Kentucky Power
Location	Maysville, KY
Cable Design	138 kV, 1500 CU — High Voltage Cable
Length	5,400 Circuit Feet
Subcontractors(s)	B+B Electric
Scope	Constructed new concrete encased ductbank, pulled in new underground high voltage cable, built terminations and completed final system acceptance testing. Due to weather conditions temporary termination shelters were constructed to allow construction of the cable terminations.



Cable Termination Shelter.



Cable Installation.