

Kerite Cable Services Project Profile

Project	Cheswick Power Station
Client	The Washington Group — Duquesne Light Co
Location	Cheswick, PA
Cable Design	138 kV, 500 kcmil CU — High Voltage Cable
Length	800 Circuit feet
Subcontractors(s)	Client supplied (Sargent Electric)
Scope	Supervised cable pulling through existing ductbank and cable tray. Performed an 8kV-DC jacket test. Installed six high voltage terminals and cable sheath bonding accessories. Upon completion of the installation, a final system acceptance test was conducted by KCS technicians.



Completed HV terminations.



Cable pulled through tray.