

Kerite Cable Services Project Profile

Project	Lubrizol 138kV Installation
Client	Dashiell Corporation
Location	Deer Park, TX
Cable Design	138kV, 500 kcmil CU
Length	200 circuit feet
Subcontractors(s)	Anderson & Wood Construction Co., Inc.
Scope	Oversaw installation of a two 138kV circuits (6 lengths). Scope included performing 10kV jacket integrity test, assembling twelve G&W PAT140 Outdoor In Air Polymer Terminations and completing a DC Hi-pot test at 240kV DC



Cable installed in concrete trench



Battling the hot summer Texas sun while assembling terminations.

