

Kerite Cable Services Project Profile

Project	Paragould Light Water & Cable 69kV Cable Installation
Client	Paragould Light Water & Cable
Location	Paragould, AR
Cable Design	69 kV, 750 kcmil CU
Length	800 Circuit Feet
Subcontractor(s)	Anderson & Wood Construction Co., Inc.
Scope	Prime contractor for the new installation of a single 69kV circuit. The new Kerite 69kV system was pulled through the owner furnish concrete encased duct bank. KCS technicians installed 6- EHVT692-SG heat shrink terminations and completed final acceptance testing.



KCS technicians assembling the final Tyco Heat Shrink Termination on the 60' riser pole.



Termination connected to lightning arrester with 1-1/2" IPS copper bus tubing. Jumpers from the overhead 69kV line were attached to the NEMA 4 hole pad on the top of the termination.