

Kerite Cable Services Project Profile

Project	John H. Kerr Powerhouse
Client	Koontz Electrical Company Inc.
Location	Boydton, Virginia
Cable Design	115kV, 500kcmil CU – XLPE High Voltage Cable
Length	Cable supplied and installed by others
Subcontractors(s)	Anderson and Wood
Scope	Installed forty-two high voltage cable terminations and ground cable sheath to terminations on XLPE cable. Upon completion of installation, a final system acceptance test was conducted.



Termination with stress cone and finished termination.



Using specially tools to remove insulation shield.