

Kerite Cable Services Project Profile

Project	Kent County Substation
Client	National Grid
Location	Warwick, Rhode Island
Cable Design	115 kV, 2000 kcmil Cu — High Voltage Cable
Length	200 Circuit feet
Subcontractor(s)	Central Connecticut Cable Company
Scope	Pulled three lengths of cable through an existing duct bank. Performed a jacket test on each length of cable. Installed six high voltage cable terminations and all required sheath bonding accessories. Upon completion of installation, a Megger acceptance test was conducted by KCS technicians.



Kent County site, working with close clearance to overhead lines.



Completed structure with polymer terminations.