

Kerite Cable Services Project Profile

Project	City of Ocala, Substation
Client	Elite Construction of Ocala, Inc.
Location	Ocala, Florida
Cable Design	69 kV, 1500 kcmil Cu — High Voltage Cable
Length	760 Circuit feet
Subcontractors(s)	Elite Construction of Ocala, Inc.
Scope	Direct buried three lengths of cable. Performed a 10 kV-DC jacket test on each length of cable. Installed six high voltage cable terminations, all required sheath bonding accessories, bus work and arrestors. Upon completion of installation, a final system acceptance test was conducted by KCS technicians.



Pulling cable up 90ft pole.



Completed terminations with link box and bus work.