

Kerite Cable Services Project Profile

Project	Glenbrook Substation
Client	NUSCO
Location	115 kV, 1500 kcmil CU — High Voltage Cable
Cable Design	3,000 Circuit feet
Length	3,000 Circuit feet
Subcontractor(s)	Central Connecticut Cable Company
Scope	Installed into existing conduits within a substation new 115 kV circuit feeders. Installed new G&W high voltage cable terminations. Final system Hi-pot acceptance testing was completed by KCS technicians.



Cable Termination Scaffolding



Cables Ready for Termination