

## Kerite Cable Services Project Profile

<b>Project</b>	Substation 282 Circuit 282-521
<b>Client</b>	Eversource
<b>Location</b>	Waltham, MA
<b>Cable Design</b>	115 kV, 1,500 kcmil Cu
<b>Length</b>	1,800ft
<b>Subcontractor(s)</b>	Central Connecticut Cable Co., Inc.
<b>Scope</b>	Prime contractor for the supply and install of three lengths of 1500 kcmil 115 kV cable. Laid cable in trench, performed 10 kV jacket integrity test, completed six 3M TP-123 terminations and performed 226 kV DC Hi-Pot test upon completion of the project.



Laying cable in trench. Cable was direct buried.



Completed 3M TP-123 terminations.