

Kerite Cable Services Project Profile

Project	Thermal Energy Corporation (TECo)
Client	Burns & McDonnell
Location	Houston, Texas
Cable Design	138 kV, 750 kcmil Cu — High Voltage Cable
Length	Two circuits: 900 circuit feet each
Subcontractors(s)	Anderson & Wood Construction Co., Inc.
Scope	Pulled six lengths of cable through an existing duct bank. Performed a jacket test on each length of cable. Installed twelve high voltage cable terminations with extra creep and all required sheath bonding accessories. Upon completion of installation, a final system acceptance test was conducted by KCS technicians.



Cable pulling across substation due to space constraints.



Completed terminations within substation.