

Kerite Cable Services Project Profile

Project	Canal Street Substation
Client	Eversource
Location	Southington, CT
Cable Design	115 kV, 1,000 kcmil Cu
Length	600ft
Subcontractor(s)	Central Connecticut Cable Co., Inc.
Scope	Prime contractor for the supply and install of three lengths of 1000 kcmil 115kV cable. Scope included pulling cable in owner-installed concrete-encased duct bank, performing 10 kV jacket integrity test, completion of six G&W PAT 140 terminations and performing 226 kV DC Hi-Pot test upon completion of the project.



Pulling cable into duct bank



KCS technicians assembling a G&W PAT 140 termination