

Kerite Cable Services Project Profile

Project	Seattle City Light — Canal Substation
Client	City of Seattle
Location	Seattle, Washington
Cable Design	115kV, 750 kcmil Cu — High Voltage Cable
Length	200 Circuit feet
Subcontractors(s)	Client supplied (local Power Company)
Scope	Emergency replacement of failed XLP circuit with Kerite Cable. Supervised pulling of cable through existing duct bank. Installed six high voltage terminals and sheath bonding accessories. Project was completed within six working days.



Failed termination that was replaced.



Platform constructed to facilitate installation of termination.