

Kerite Cable Services Project Profile

| | |
|--------------------------|---|
| Project | Allentown Center Substation – Emergency Repair |
| Client | PP&L Electrical Utility Corp. |
| Location | Allentown, Pennsylvania |
| Cable Design | No cable was sold for this project. Materials were for terminations parts only. |
| Length | 400 linear feet in conduit, 100 linear ft direct buried |
| Subcontractors(s) | Anderson and Wood |
| Scope | Project consisted of the removal and replacement of 500ft of cable. 400ft of which was removed from duct and the reaming 100ft was direct buried. The duct bank was cleaned and proofed and new cable installed. Six high voltage terminations were installed. Six high voltage splices were installed. All necessary sheath bonding was installed. |



Installation of splice.



Pulling cable in substation.