

## Kerite Cable Services Project Profile

<b>Project</b>	MidAmerican – 69kV Installation
<b>Client</b>	PAR Electrical Contractors Inc.
<b>Location</b>	Des Moines, Iowa
<b>Cable Design</b>	69kV, 1500kcmil CU – High Voltage Cable
<b>Length</b>	274 circuit feet
<b>Subcontractors(s)</b>	Anderson & Wood
<b>Scope</b>	This project was an emergency repair which included the installation of six high voltage cable terminations, six lighting arrestors, and all required sheath bonding accessories. An 822 ft piece of cable in stock was used to expedite the replacement process. Upon completion of installation, a final system acceptance test was conducted by KCS technicians.



Crews working on pole outside of substation.



DC HiPot testing.