



Kerite Cable Services Project Profile

Project Agawam Substation

Client NUSCO

Location Agawam, Massachusetts

Cable Design 115kV, 2000kcmil Cu — High Voltage Cable

Length 600 circuit feet

Subcontractors(s) Central Connecticut Cable Company

Scope Pulled three lengths of cable through an existing duct bank.

Performed a 10kV jacket test on each length of cable. Installed six high voltage cable terminations and all required sheath bonding accessories. Upon completion of installation, a final system acceptance test was conducted by KCS technicians.



Demonstrated ability to safely install termination and cable near energized lines



Completed terminations on 90ft pole